BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: EE/RRND/Tend/04/2019-20 Date: 12.06.2019

Indet No: BBMP/2018-19/WS/WORK_INDENT34923/CALL-2

SCHEDULE -B

Name of Work: Development works for Providing Drinking Water Facility in ward no 16

Sl.No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	1124.89	Earthwork excavation by Manual means for foundaction of buildings, water supply, sanitary lines and electrical conduits etc., either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications.	Cum	599.00	Rupees Five Hundred Ninety Nine Only
2	2070.00	Providing and fixing to wall, ceiling and floor high density polyethylene pipes 6.00 kgf/sq.cm working pressure pressura outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. for 63MM dia	Rmtr	413.00	Rupees Four Hundred Thirteen Only
3	90.00	Providing and fixing in position brass bib cock of approved quality nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications for 25mm dia	Nos	262.00	Rupees Two Hundred Sixty Two Only
4	108.00	Providing and fixing in trenches galvanised / mild steel tubes (medium grade) nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications.for 25mm dia	Rmtr	278.00	Rupees Two Hundred Seventy Eight Only
5	9.11	Providing and laying in position plain cement concrete of mix 1:2:4 with OPC cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @ 0.53cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	6027.00	Rupees Six Thousand Twenty Seven Only
6	1117.80	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications allow 60% of rate considered under item.	Cum	135.00	Rupees One Hundred Thirty Five Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned by CamScanner